

Name of the work : **Demolition and Reconstruction of Market Complex for Bhoma - Adcolna Panchayat - Civil, Plumbing, Electrical, Lifts and Fire Fighting Works**

CORRIGENDUM – I TO TENDER NOTICE NO. GSIDC/ENGG. /NIT-163/2018-2019 DATED 21st DECEMBER 2018

Name of Work: Demolition and Reconstruction of Market Complex for Bhoma - Adcolna Panchayat - Civil, Plumbing, Electrical, Lifts and Fire Fighting Works.

Sr. No	Document Name	Item no.	Current	Read as
1.	Bill of Quantities Vol-III	F6	Vaccum dewatering of laid concrete for roads/ areas using Tremix machinery including formwork with MS channel/ angle sections on sides of concrete with proper supporting system, surface/screed & needle vibrating & levelling of concrete. Vaccum dewatering should be done using suction mats (spread on surface) & suction pump, power floating/ troweling using screen floater, manual spreading of hardening compound (if any), smooth/rough/broom finish to the required slope, camber & level, groove cutting (upto 10mm wide x50mm deep) for contraction/expansion, construction & longitudinal hoints, Providing dowel bars with sleeve/tie bars, filling two component polysuphide sealant/joint filler (Bitumen hot sealing compound: Grade A), taping with masking tape etc complete. (Concrete, reinforcement, Dowel Bar with sleeve/tie bar Reinforcement, tarpaulin sheet to be paid separately)	Providing and laying vitrified unglazed porcelain tactile floor tiles in different sizes (thickness to be specified by the manufacturer) and conforming to IS:15622 of approved make in colours and shades as specified laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand) including grouting the joints with white cement and matching pigment etc., complete